سي اند جي الخليج لتصنيع المعدات ذ.م.م
C & J GULF EQUIPMENT MANUFACTURING L.L.C
P.O. Box : 7702, Abu Dhabi, United Arab Emirates
Tel. : +971 2 5553 453 Fax : +971 2 5553 966 E-mail : cjengsales@cjengg.com

Ref.: **CNJ/142676/01/2025** **Date: Jan 29, 2025**

To:
M/s Descon Engineering
Abu Dhabi – UAE

Kind attention: **Mr. Harun Khan**
Incharge Subcontracts

Project: **Procurement & Construction Contract for providing standby PSVs and isolation valves at inlet and outlet of PSVs- STEEL STRUCTURE FABRICATION**

Subject: **Techno Commercial Proposal – Steel Structural work**

Dear Sir,

We thankfully acknowledge receipt of your subject enquiry and are pleased to submit our Techno-Commercial offer for structural work for the information given in the RFQ, for your kind consideration.

We hope you will find our offer in-line with your requirement. However, we shall be pleased to submit additional clarification/information which you may require.

We thank you and look forward to be of service to your prestigious company.

Best regards,

For C&J Gulf Equipment Manufacturing LLC.

Subash Valrani
Business Unit Head.

TECHNICAL PROPOSAL

A. C&J Scope of Works:

I. Structure Works:

1. Supply of skilled manpower, equipment, consumables, tools, tackles, supervision and other resources to carry out shop structural steel fabrication works.
2. Welding consumable shall be 3.1 certified.
3. C&J Existing WPS/PQR will be in accordance with ASME SEC IX. Any new qualification shall be at additional cost.
4. NDT-MPI-10% For primary and secondary members.
5. Painting system as per Adnoc specification. Procurement of Paint and other consumable shall be under Descon Scope.
6. Tagging & marking included in C&J scope.
7. To provide a Daily/weekly progress report to client.
8. Preparation and submission of inspection dossiers including all inspections, QA/QC documents, inspection clearance, etc.
9. Packing list with ID reference for each shipment will be provided along with shipment.
10. Free access to client's representative to check the quality and progress of work during normal working hours.
11. Proper packing and wooden blocks to suit safe loading / transportation through trailer.
12. All jobs shall be executed in accordance with the client's drawings, specifications, standards and procedures.
13. Client's Health and Safety Environment (HSE) program will be followed during execution of the job.

B. Descon to provide:

1. Approved for construction drawings for structural work.
2. Steel structure material required for Fabrication
3. Third Party Inspection if any.
4. Transportation to and from C&J workshop.
5. Welding / Painting inspector required, if any. (CSWIP 3.1 / 3.2 & BAGAS / NACE).

C. Galvanizing & Surface Preparation & Painting:

1. Painting will be carried out as per painting specifications and procedures.

D. General Considerations:

1. This offer is in strict accordance to the parameters as stated in our scope of works. Any deviations may have a cost impact.
2. C&J will not be responsible for any modification after material dispatch and signing of release note by client representative.

E. Documentations:

1. ITP & PQP will be provided before start of the job.
2. Material test certificates.
3. Fabrication reports.
4. Painting reports.

F. Remarks:

1. Material test certificates for welding electrodes supplied by C&J will be provided.
2. Any eventual additions and variations during project execution shall be considered as additional work and shall be charged extra with agreement in writing from client

G. Quality Control:

1. Quality planning, execution and certification shall be done by C&J in-house QC personnel and final quality documents shall be submitted to client along with other commercial documents. Client can be present for all in-house inspections and final inspection at shop prior to dispatch, which shall be deemed sufficient and final for techno-commercial acceptance and approval and for invoicing purposes.
2. C&J shall carry out the necessary quality control inspections, including inspection of free issue material, consumables, in-house fabrication, measurements, procedures and documentation in accordance with client/project requirements.

H. Exclusions:

1. Mechanical design, shop fabrication drawing preparation and approval if any.
2. Check Testing if any.
3. Welding / Painting inspector if any (CSWIP 3.1/3.2 & BGAS / NACE).
4. Any kind of site work (Field joint, Installation, Testing etc.)
5. Any kind of NDE apart from that mentioned in the scope of works.
6. Installation, erection, commissioning if any.
7. Third Party Inspection (NACE, BAGAS, CSWIP 3.1/3.2)
8. Structural steel material/Fasteners.

I. Price Offer: (Commercial)

1. Refer attached Annexure 01 (CNJ-142675-01-2025)

J. Terms & Conditions:

1. Payment terms –30 Days Credit basis from the submission of DESCON Certified invoice in MBZ office with SES No mentioned on it. SES number shall be provided one weeks' time.
2. Quoted price shall be excluding Vat & Custom duty.
3. Partial invoicing is acceptable to client.
4. Invoice certification and verification by client shall be deemed adequate for processing the invoice (without waiting for end user's verification).
5. Any discrepancy in the invoice shall be adjusted in the subsequent invoice.
6. Any amendments due to increase in quantity shall be done parallel so as to avoid delays in processing the invoice payment.
7. Finished product to be shifted immediately after release note receipt
8. Work need not start until we receive the complete IFC Drawings.
9. Validity - Offered price is valid up to 30 days from the proposal date

K. Delivery Period:

1. Delivery: Mutually discussed and agreed upon PO receipt.

L. Responsibility Matrix:

Split of Responsibility Matrix for Structural Steel Works			
Item	**Description**	**DESCON**	**C & J**
1	Supply of approved Structural IFC drawings and project specifications	X	
2	Supply of Structural Items such as plates, Beams, Channels.	X	
3	Collection of finished steel works	X	
4	Painting & Blasting Material in C&J Scope.		X
5	NDT-MPI-10% For primary and secondary members.		X
6	All mandatory PPE and job specific PPE		X
7	QA/QC documentation as per project specifications		X
8	Supply of resources, manpower and equipment fully compliance with project requirement for satisfactory completion of job at shop.		X
9	Supply of all consumables required for Structural job		X
10	Preparation of quality control plan or (ITP) and any other job specific documents required by client/end users.		X
11	Comply with client HSE and Quality requirements		X
12	Overall project management and supervision for shop fabrication		X
13	Submission of Daily/weekly progress report		X
14	Tagging and marking of Structural members.		X

Thanking you and assuring you of our best services at all times.

Best regards,
For C&J Gulf Equipment Manufacturing LLC.

Ahire Sachin
Sr Planning Engineer

Subash Valrani
Business Unit Head

CNJ-142676-01-2025-R0-ANNEXURE -1

Procurement & Construction Contract for providing standby PSVs and isolation valves at inlet and outlet of PSVs- STEEL STRUCTURE FABRICATION

Revision.00 **Date** **29/01/2025**

MATERIAL PRICE

Sr No	3	Steel work	KG PER METER FOR PIPE	Unit	Unit Qty	Total Weight in KG	PER KG/PER METER	T. Amount in AED	REMARKS
1	3.1	Provide and fabrication of Steel Profile Grade S275JR or ASTM A36	0	KG	1.00	4,702.73	3.20	15,048.75	**for Supports Material price**
2	3.2	Provide and fabrication of steel plate Grade S275JR or ASTM A36	0	KG	1.00	940.54	3.20	3,009.73	
3	3.3	3" NB SCH 40, ASTM A 333 Gr.6	11.29	M	12.00	135.48	92.30	1,107.60	
4	3.4	4" NB SCH 40, ASTM A 333 Gr.6	16.02	M	24.00	384.48	138.24	3,317.76	
5	3.5	6" NB SCH 40, ASTM A 333 Gr.6	28.26	M	12.00	339.12	231.12	2,773.44	
6	3.6	**3"NB sch 40S ASTM A312 TP 304L**	11.29	M	**12.00**	135.48	365.25	4,383.00	
7	3.7	**6" RE-PAD ASTM A312 TP 304L**	28.26	M	**6.00**	169.56	850.25	5,101.50	
8	3.8	**10" NB RE-PAD ASTM A358 TP 304L**	60.31	M	**6.00**	361.86	2,259.36	13,556.16	
9	3.9	**3" RE-PAD ASTM A312 TP 304L**	11.29	M	**6.00**	67.74	365.25	2,191.50	
10	3.10	2" NB Pipe SCH 40 Matl CS SMLS ASTM A 106 Gr.B	5.44	M	**12.00**	65.28	23.76	285.12	
11	3.11	Mild steel plate Gr.43A		KG	1.00	500.00	3.20	1,600.00	
12	3.12	M20X90 Long Bolts HEX HD & Nut to BS 4190 Gr.8.8		NOS	30.00		12.50	375.00	
SUB TOTAL AMOUNT IN AED (A)								**52,749.56**	

CNJ-142676-01-2025-R0-ANNEXURE -1

FABRICATION,NDT AND PAINTING PRICE

Sr No	3	Steel work	KG PER METER FOR PIPE	Unit	Unit Qty	Total Weight in KG	PER KG/PER METER	T. Amount in AED	REMARKS
1	3.1	Provide and fabrication of Steel Profile Grade S275JR or ASTM A36	0	KG	1.00	4,702.73	7.25	34,094.82	**for Supports Fabrication and painting included with 10% MPI/DPT**
2	3.2	Provide and fabrication of steel plate Grade S275JR or ASTM A36	0	KG	1.00	940.54	7.25	6,818.92	
3	3.3	3" NB SCH 40, ASTM A 333 Gr.6	11.29	KG	12.00	135.48	7.25	982.23	
4	3.4	4" NB SCH 40, ASTM A 333 Gr.6	16.02	KG	24.00	384.48	7.25	2,787.48	
5	3.5	6" NB SCH 40, ASTM A 333 Gr.6	28.26	KG	12.00	339.12	7.25	2,458.62	
6	3.6	**3"NB sch 40S ASTM A312 TP 304L**	11.29	KG	12.00	135.48	12.25	1,659.63	
7	3.7	**6" RE-PAD ASTM A312 TP 304L**	28.26	KG	1.20	33.91	12.25	415.42	
8	3.8	**10" NB RE-PAD ASTM A358 TP 304L**	60.31	KG	0.60	36.19	12.25	443.28	
9	3.9	**3" RE-PAD ASTM A312 TP 304L**	11.29	KG	0.60	6.77	12.25	82.98	
10	3.10	2" NB Pipe SCH 40 Matl CS SMLS ASTM A 106 Gr.B	5.44	KG	12.00	65.28	7.25	473.28	
11	3.11	Mild steel plate Gr.43A		KG	1.00	500.00	7.25	3,625.00	
12	3.12	M20X90 Long Bolts HEX HD & Nut to BS 4190 Gr.8.8			30.00	30.00	12.50	375.00	
SUB TOTAL AMOUNT IN AED (B)								**54,216.66**	
TOTAL AMOUNT IN AED (A+B)								**106,966.22**	

Vendor: C&J Gulf Equipment Manufacturing LLC

Sachin Sudhakar Ahire

Sr.Planning Engineer

Vendor: C&J Gulf Equipment Manufacturing LLC

Subash Valrani

Business Unit Head