سي اند جي الخليج لتصنيع المعدات ذ.م.م
C & J GULF EQUIPMENT MANUFACTURING L.L.C
P.O. Box : 7702, Abu Dhabi, United Arab Emirates
Tel. : +971 2 5553 453 Fax : +971 2 5553 966 E-mail : cjengsales@cjengg.com

Ref.: **CNJ/142923/04/2026** Date: 14th April 2026

To:
M/s. Probus Engineering and Construction Pte.Ltd- Abu Dhabi
Sheikh Zayed Bin Sultan St - Al Zahiyah - E16 01, Abu Dhabi, UAE
Tel No. +971 2 677 3144 Mobile No. +971 58 264 7766
Email Address: hkongath@probusec.com Website: www.probusec.com

Kind attn.: **Hashim Kongath| Procurement Engineer**

Subject: Supply, Fabrication, Galvanizing & Painting works of structural Steel for Hypochlorite Injection Skid Shelter & Pump & Portable Water Tank Shelter

Reference: **Your email dated 10th April 2026**

Dear Sir,

We thank you very much for sending enquiry for the subject work. Based on the details received from you, we are pleased to submit our revalidated Techno-commercial proposal as detailed below for your kind consideration.

A. SCOPE OF WORK

All scope of work based on the below drawings provided by client and used as the only reference
Hypochlorite Injection Skid Shelter RDS-5-ASAB – (14 15 76 1609 B 1&2, 14 15 76 1610 B 1/1)
Pump & Portable Water Tank Shelter RDS-5-ASAB – (14 15 76 1605 B 1&2, 14 15 76 1603 B 1/1)

- Supply of material, fabrication, painting, galvanizing of Structural Steel Work
- Raw material procurement with 3.1 MTC's
- Fabrication of Structures
- NDT - 10% of MPI & 10% of RT Considered
- All Members shall be Hot Dipped Galvanized
- Painting as per AGES-SP-01-002
- All parts will be labeled and packaged for easy reassembly.
- Fabrication will adhere to strict dimensional and alignment tolerances to support seamless integration during assembly.
- Delivery-Ex Works

B. BASIS OF PRICE

1. All **detailed fabrication drawings, GA drawings, and design responsibility** shall be provided by the Client.
2. The fabrication works will be carried out at our workshop in Musaffah, Abu Dhabi. Prices are based on the **material grades, quantities, and weights** stated in this offer.
3. Fabrication shall commence only upon receipt of **Approved-for-Construction (AFC) drawings**.
4. The supply of material based on Annexure 1 will be as per the grade mentioned in the below table. We will provide necessary material certificates issued by mill for the materials procured by us (Test Certificates as per EN 10204 3.1).

Sl. No.	Description	Material	Scope of Supply
1	Structural Steel	S275 JR	C&J GEM LLC

5. The estimated weight of structural steel is indicated below and is prepared based on Drawings provided by the client (14 15 76 1609 B 1&2, 14 15 76 1610 B 1/1), (14 15 76 1605 B 1&2, 14 15 76 1603 B 1/1). <u>Any increase in weight may warrant a revised offer comparatively.</u>

Sl. No.	Item Description	Weight/Inch Dia	Remark
1	Pump & Portable Water Tank Shelter (1 Qty)	20.2 MT	C&JGEM LLC
2	Hypochlorite Injection Skid Shelter (1 Qty)	10.7 MT	C&JGEM LLC

* Note – Hypochlorite Skid Weight consists of Sag Rod (Round Bar 16 Dia), Structural Connection & Support Plate Details. For Pump & Portable water shelter we have considered only Sag Rod as plate details are not provided.

6. The cost of the supply of material for General Structural Steel works shall be based on the prevailing market rates at the time of the awarding of PO, due to the current sudden variations in steel pricing.
7. We have considered provision of complete manpower including project management team, welders, fitters, skilled workers, specialized technicians and support staff.
8. Welding electrodes and other consumable shall be supplied by C&J.
9. Existing WPS/PQR shall be utilized for the subject job, any requirements for qualification of new PQR shall be considered as additional requirement.
10. All welding works shall be carried out by qualified welders certified by third party agency. 100% visual inspection of weld joints is considered.
11. Free Access to client representatives to check the quality and progress of work during normal working hours.
12. QA/QC dossiers shall be provided as per C&J standard quality procedure.
13. Loading on to client's truck for delivery.
14. Transportation to client facility is not considered.

15. For Pump & Portable water Tank a single Platform (8 Mtrsx1.4 Mtrs) at EL 105.450 is considered. Gratings of 2.2 Sq. Mtrs is considered. Hand Rails for the platform is not considered.
16. Any Aluminum Roofing Sheeting & Profile roofing Sheeting is not considered in our price. Fasteners are not considered.
17. Prices are based on estimated quantities and weights stated in this offer. Any increase arising due to design changes, drawing revisions, or additional client requirements shall be charged on a proportional basis.

C. GENERAL CONSIDERATIONS

1. This quotation, together with the Purchase Order, approved scope, and agreed drawings, shall form the basis of the contract. In case of any conflict, the terms of this quotation shall prevail unless otherwise agreed in writing.
2. Fabrication shall commence only upon receipt of Approved-for-Construction (AFC) drawings. Any revision, modification, or change after commencement shall be treated as a variation with cost and schedule impact.
3. Any change in scope, drawings, quantities, specifications, inspection requirements, or schedule shall be executed only through a mutually agreed Variation Order (VO) with corresponding cost and time adjustment.
4. Any delay, shortage, or defect in client-supplied materials, equipment, or assemblies shall entitle C&J to corresponding schedule extension and, where applicable, cost adjustment.

D. MANPOWER & FABRICATION PRACTICE

1. Complete manpower including welders, fitters, technicians, and supervisory staff is included
2. Welding consumables shall be supplied by C&J
3. Existing approved **WPS/PQR** shall be used
4. Qualification of new PQRs, if required, shall be treated as **additional**
5. All welding shall be performed by **qualified welders**
6. **100% Visual Inspection (VT)** of welds is included

E. EXCLUSIONS

1. Third-party inspections not stated in the PO
2. Any NDT other than 10% MPI & 10% of RT
3. Supply of fasteners, gaskets, and non-metallic items
4. Transportation and delivery to site
5. Engineering, GAD, and fabrication drawing preparation
6. Check testing of materials.
7. Qualification of new PQRs

8. Site installation, commissioning, or site works
9. Electrical work
10. As-built drawings are excluded unless explicitly stated in the Purchase Order.
11. Structural Connection Plate & Support Plate Details for Pump & Portable Water Tank Shelter
12. Any Aluminum Roofing Sheeting & Profile roofing Sheeting.
13. Hand Rails & Ladder for Platform

F. INSPECTION & ACCEPTANCE

- Inspection shall be carried out at C&J workshop during normal working hours
- Client representatives may witness inspections with prior coordination
- **Shop inspection and acceptance shall be deemed final** for invoicing and dispatch
- C&J shall not be responsible for any modifications or claims raised **after dispatch and release note signing**

G. PRICE OFFER: EX-WORKS EXCEPT FOR GENERAL STRUCTURAL STEEL WORK

Sr. No.	Item Description	QTY	Unit Price AED	Total Price AED
1	Supply, Fabrication, Galvanizing & Painting works of structural Steel for A. Hypochlorite Injection Skid Shelter (1 Qty) B. Pump & Portable Water Tank Shelter (1 Qty)	LS	440,000.00	440,000.00
	Grand Total Price in AED			**AED 440,000**
[AED Four Hundred & Forty Thousand only] Excluding VAT/ Custom Duty				

Note: The cost of the supply of material for General Structural Steel works shall be based on the prevailing market rates at the time of the awarding of PO, due to the current sudden variations in steel pricing.

H. DELIVERY TERMS

- Delivery shall be **Ex-Works C&J workshop for all items**
- Risk and responsibility shall transfer to the Client upon loading onto client's truck

I. TIME SCHEDULE

The Fabrication timeline shall be confirmed and agreed upon at the time of order confirmation based on project requirements. Delays in the above shall automatically extend the delivery schedule.

J. VARIATION/ CHANGE CONTROL

Any change in scope, drawings, quantities, specifications, inspection requirements, or schedule shall be executed only through a **mutually agreed written Variation Order**, including cost and time impact.

K. PAYMENT TERMS

The payment shall be released as per following break-up;

- ***Advance payment equivalent to 50% of PO*** shall be payable upon return of the duly acknowledged Purchase Order and submission of our proforma invoice, with a payment term of 7 days. This is in account of the material supply for Structural Steel, Paint, Consumables, Galvanizing Costs, etc.

- ***Balance payment shall be made as per the below milestones.***
- 30% after the Galvanizing & Painting of Structures with respect to the tonnage completed, with a payment term of 15 days.

- Balance 20% shall be payed as CDC after 'release for shipping' of Structural Fabrication & Submission of Invoice.

C&J reserves the right to suspend work and withhold delivery in case of delayed or non- payment without any liability or penalty.

L. FORCE MAJEURE

Delays due to events beyond contractor's control such as war, extreme weather, government restrictions, or force majeure conditions shall entitle schedule extension without penalty.

M. VALIDITY

This offer is valid for **7 days** from the date of submission.

We trust the above meets your requirements and look forward to your valued order. Please feel free to contact us for any clarification.

Thanking you and assuring you of our best services at all times. For **C&J Gulf Equipment Manufacturing LLC.**

Bilal Ahmed
Cost & Estimation Engineer.

Datta C. Sawant
Sr. Mechanical Engineer

Arjun Gopakumar
Business development